GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Rural Development – Mahatma Gandhi National Rural Employment Guarantee Scheme (MGNREGS) - Revision of Rural Standard Schedule of Rates, 2021-2022 (RSSR 2021-2022) – Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RD.II) DEPARTMENT

G.O.Ms.No.66 **Dated:17.09.2021**

Read the following:

1. G.O.Ms.No.27, PR&RD (RD.II) Dept., Dated:22.04.2021.
2. From the CPR&RD e-file No.PRR05-17022(32)/1/2021-EGS WORKS SEC-CORD, Dt.29.08.2021.

<<0>>

ORDER:

In the G.O first read above, Government have issued orders modifying Rural Standard Schedule of Rates from Rs.237/- to Rs.245/- per day for the year 2020-2021 as per the wage rate enhanced by the Government of India under MGNREG Scheme for the year 2021-2022.

2. In the reference second read above, the Commissioner, Panchayat Raj & Rural Development, AP has submitted proposal for revision of task rates of various items in the RSSR Rates for Financial Year 2021-2022, based on the SORs finalized by the NIRDPR in connection to the instructions of MoRD, GoI and as per the opinion of technical Committee constituted for this purpose.

3. Government after examination of the proposal, hereby modify the task rates of Rural Standard Schedule of Rates of the Financial Year 2021-2022 as detailed in the Annexure to this order superseding orders issued in the reference first read above.

4. The Commissioner, Panchayat Raj and Rural Development, AP shall take necessary further action in the matter accordingly.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

GOPAL KRISHNA DWIVEDI
PRINCIPAL SECRETARY TO GOVERNMENT

To:

The Commissioner, Panchayat Raj and Rural Development, AP., Guntur District with a request to communicate the same to all the concerned.
All the District Collectors and District Programme Coordinators, MGNREGS in the State.
All the Project Directors, DWMA & Addl. District Programme Coordinators, MGNREGS in the State.
All the Project Directors, DRDAs and Additional District Programme Coordinators, MGNREGS in the State.
All the Chief Executive Officers, ZPs and Additional District Programme Coordinators, MGNREGS in the State.
The Project Officer, ITDA and Additional District Programme Coordinators Parvathipuram (Vizianagarm), Srisailam (Kurnool), Paderu (Visakhaptnam), Seethampeta (Srikakulam), Rampachodavaram (East Godavari) & KR Puram (West Godavari).

Contd...2

Copy to:

The Secretary, Water Resources Department
The Prl. Secretary, Tribal Welfare Dept.,
The Prl. Secretary, R&B.
The Prl. Secretary, EFS & T Dept.,
The Prl. Chief Conservator of Forests, Guntur.
The Commissioner Disaster Management and EO Secy. to Govt.
The Commissioner, Tribal Welfare.
The Chairman and Members of Technical Committee.
The Engineer-in-Chief, Panchayat Raj Dept.
The Engineer-in-Chief, Irrigation Dept.
The Chief Engineer, Tribal Welfare
The Secretary, APSEG Council.
The PS to Hon'ble Minister (PR RD, M&G)
The PS to Prl. Secretary to Government, PR&RD
SF/SC

//FORWARDED :: BY ORDER//

SECTION OFFICER

ANNEXURE
(to G.O.Ms.No.66, PR&RD (RD-II) Department, dated:17/09/2021)

S. No.	Category No.	Item of Work	Unit	Rate per unit (Rs)
1		Unskilled wage rate	day	245/ -
	Jungle/Bush clearance			
2	a	Clearing jungle including uprooting rank vegetation, grass, brush wood, bushes, shrubs, saplings and trees of girth upto 30 cm measured at a height of 1 m above ground level and removal of stumps of such trees cut earlier, removal of rubbish upto a distance of 50 m outside the periphery of the area cleared and stacking of serviceable material to be used or auctioned.(Medium and Dense Shrub /Besharam/ Rubber plants) (MoRD Code:C2)	Sqm	7.70
	b	Light shrub Clearing jungle including uprooting rank vegetation, grass, brush wood, bushes, shrubs, saplings and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared .(Light shrub)	Sqm	6.06
3		Cutting and clearance of bushes, shrubs ankara/ipomoea, julie flora typha etc on canals, water courses, bunds in dry/moist/slushy conditions including disposal. Less/more than 50 % coverage area		
	a	Thin stemmed Juliflora (stem with periphery upto 150 cms)/ thick shrub(MoRD Code:A17(i)&(ii))	Sqm	14.14
	b	Thick stemmed Juliflora (stem with periphery more than 150 cms	Sqm	22.86
4	Removal of stumps			
	a	Removal of stumps of girth 30cms to 99cms (small stumps)	each	176.93
	b	Removal of stumps of girth 100cms to 199cms(medium stumps)	each	199.01
	c	Removal of stumps of girth 200cms to 299 cms(large stumps)	each	258.70
	d	Removal of stumps of girth 300cms to 399 cms(large stumps)	each	338.33
	e	Removal of stumps of girth 400cms to 499 cms(large stumps)	each	437.86
	f	Removal of stumps of girth 500cms to 599 cms(large stumps)	each	537.33
5		Removal of water hycinth up to 30cms thick	Sqm	7.54
6		Removal of water hycinth of more than 30cms thick	Sqm	10.31
7		Earthwork in excavation by manual means exceeding 1.5 m in width taking out the excavated soil and disposal as directed by engineer in charge (For works Community soak pits/Feeder channels/Supply channels etc)		

	a	*Ordinary soil, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A1.1(i)	Cum	194.20
	i	Ponds (Farm pond, Dugout pond etc) upto 1.5mt depth	Cum	225.00
	ii	*Ponds*(Farm pond, Dugout pond etc) above *1.5mt depth*	Cum	315.00
	b	*Hard soil, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A1.2(i))	Cum	229.40
	i	*Ponds* (Farm pond, Dugout pond etc) upto 1.5mt depth	Cum	247.07
	ii	*Ponds* (Farm pond, Dugout pond etc) above *1.5mt depth*	Cum	330.80
	c	*Mixture of gravel, pebbles and SDR soils, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A1.3(i))	Cum	272.91
	i	*Ponds* (Farm pond, Dugout pond etc) upto 1.5mt depth	Cum	272.91
	ii	*Ponds* (Farm pond, Dugout pond etc) above *1.5mt depth*	Cum	331.00
8		Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods (5cm to 7 cm size) watering, compacting each layer with wooden or steel rammers and dressing up in embankment for construction of roads, flood banks, marginal banks, guide banks or filling up ground depressions including removal of small stones/pebbles, shrubs, watering (rolling with power roller to be done separately where ever required). (for /dam/Roads/canal /flood banks/water retaining structures/ tanks/ earthen bunding/ PT/MPT/Isolated Soak Pits etc.)		
	a	*Ordinary soil, Lead upto 10 m and lift upto 1.5 m* (MoRD Code:A2.1(i))	Cum	258.13
	b	*Hard soil, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A2.2(i))	Cum	272.29
	c	*Mixture of gravel, pebbles and SDR soils, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A2.3(i)	Cum	282.42
9		Excavation work by manual means in foundation trenches/ all other trenches or drains and soak pits (not exceeding 1.5 m in width) including dressing of sides and ramming of bottoms and getting out the excavated soil and disposal of surplus excavated soil as directed		
	a	*Lead upto 10 m and lift upto 1.5 m, Ordinary Soil*(MoRD Code:A4.1(i))	Cum	259.70
	b	*Lead upto 10 m and lift upto 1.5 m, hard soil*(MoRD Code:A4.1(ii))	Cum	275.00
	c	*Lead upto 10 m and lift upto 1.5 m, Mixture of gravel, pebbles and SDR soils*(MoRD Code:A4.1(iii))	Cum	290.00

10		Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 meter in width as well as 10 sqm on plan including getting out and disposal of excavated earth as directed by Engineer-in-charge (disposed earth to be neatly dressed and levelled) For Land levelling		
	a	*ordinary soil, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A5.1(i))	Cum	171.60
	b	*Hard soil, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A5.2(i))	Cum	192.28
	c	*Mixture of gravel, pebbles and SDR soils, Lead upto 10 m and lift upto 1.5 m*(MoRD Code:A5.3(i))	Cum	250.74
11		Earth work for well excavation including disposal of excavated soil, disposed soil to be levelled and neatly dressed as per direction of Engineer-in-charge		
	a	Ordinary soil, (MoRD Code:A12.1(i) to (v))		
	i	Lead upto 50 m and lift upto 1.5 m	Cum	205.00
	ii	Add for every 0.50 m after 1.5 m initial depth upto 6.0 m	Cum	14.80
	iii	Add for every 0.50 m after 6.0 m initial depth upto 10.5 m	Cum	14.85
	iv	Add for every 0.50 m after 10.5 m initial depth upto 15.0 m	Cum	18.70
	v	Add for every 0.50 m after 15 m initial depth upto 18.0 m	Cum	21.98
	b	Hard soil(MoRD Code:A12.2(i) to (v))		
	i	Hard soil, Lead upto 50 m and lift upto 1.5 m	Cum	240.00
	ii	Add for every 0.50 m after 1.5 m initial depth upto 6.0 m	Cum	20.71
	iii	Add for every 0.50 m after 6.0 m initial depth upto 10.5 m	Cum	25.57
	iv	Add for every 0.50 m after 10.5 m initial depth upto 15.0 m	Cum	28.28
	v	Add for every 0.50 m after 15 m initial depth upto 18.0 m	Cum	34.28
	c	Mixture of gravel, pebbles and SDR soils (MoRD Code:A12.3 (i) to (v))		
	i	Mixture of gravel, pebbles and SDR soils, Lead upto 50 m and lift upto 1.5 m	Cum	274.00
	ii	Add for every 0.50 m after 1.5 m initial depth upto 6.0 m	Cum	23.16
	iii	Add for every 0.50 m after 6.0 m initial depth upto 10.5 m	Cum	28.03
	iv	Add for every 0.50 m after 10.5 m initial depth upto 15.0 m	Cum	30.78
	v	Add for every 0.50 m after 15 m initial depth upto 18.0 m	Cum	36.71
12		Dressing of uneven embankments in required profile of the water courses. (MoRD Code:A15)	Sqm	16.80

13		Desilting of small earthen channels, water bodies, ponds, canals, check dams, MI tanks etc by removal of dry/saturated (not under water) silt and disposal -(MoRD Code:B1&B2)		
		Lead upto 10 m and lift upto 1.5 m	Cum	155.00
14		Construction of gravel/soil aggregate sub-base/base by providing well graded material of nominal size grading 80 mm as per Table 2.3 of IRC SP 77-2008, spreading in uniform layers appropriate grading arrangements on prepared surface, watering and compaction with 8-10 ton power roller to achieve the desired density and camber complete as per specifications contained in Para 2.2, 3.6 and 3.7 of IRC SP 77-2008 (only unskilled labour component to be measured, materials and machinery will be supplied separately). (MoRD Code:C10)	Cum	200.90
	Social Forestry, Horticulture Work and Nursery raising			
15		Digging of pits for plant in all types of soils including removal of stones etc		
	a	ordinary Soil		
	i	0.3 m x 0.3 m x 0.3 m	each	7.00
	ii	0.45 m x 0.45 m x 0.45 m	each	20.00
	iii	0.6 m x 0.6 m x 0.6 m	each	46.00
	iv	0.9 m x 0.9 m x 0.9 m	each	155.00
	b	hard Soil		
	i	0.3 m x 0.3 m x 0.3 m	each	9.00
	ii	0.45 m x 0.45 m x 0.45 m	each	26.00
	iii	0.6 m x 0.6 m x 0.6 m	each	63.00
	iv	0.9 m x 0.9 m x 0.9 m	each	185.00
	c	Mixture of gravel, pebbles and SDR soils		
	i	0.3 m x 0.3 m x 0.3 m	each	10.00
16		Preparation of nursery by clearing and levelling the site (including space between beds) for farming 10 standard beds of 10 m x 1.2 m size .	each bed	56.17
	Masonry works			
17		Breaking of stone materials including stacking (measurement of stacks should give due allowance for sinkage or shrinkage) (MoRD Code:F3.2)		
		Boulder and local stone, 25 mm and less size	Cum	95.52
18		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering but including compaction - all work up to plinth level (MoRD Code:F11(ii))	*Cum*	882.00

19		Dry random rubble stone masonry / uncoursed rubble stone masonry laid in breast walls, Gabions, retaining walls well bonded faced with selected stones and built through / bond stones evenly placed at the rate of minimum two per sqm. (MoRD Code:F14(i))		
		Lead upto 10 m and lift upto 1.5 m	*Cum*	96.14
20		Brick work with common burnt clay F.P.S. (non modular) bricks of specified class designation in superstructure/below foundation specified grate (all grades) of cement mortar.(Un skilled labour charges only) (MoRD Code:F19)	*Cum*	680.00
21		Preparation of cement mortar of any specified grade for miscellaneous works as directed at site.(Un skilled labour charges only) (MoRD Code:F24)	Sqm	387.10
22		Laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping bed blocks, anchor blocks, plain window sills,. fillets, sunken floor etc., (upto 4 m height) excluding the cost of centering, shuttering and finishing : (RCC)(Un skilled labour charges only) (MoRD Code:F26)	Cum	1151.60
23		Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 1.50 mts in silt in canals, channels and drains	Cum	107.11
24		Earth work Excavation and depositing on bank with initial lead of 10 mt and initial lift of 1.50mts in sandy soils or loose soils/wet sand not under water		
		Land levelling for land development and Flood control Project	Cum	80.93
		Benching with 0.45mx 0.45m size and 0.60mx0.30m size	Rmt	36.68
	Carrying of earth / gravel by head loads – Leads & Lifts			
25	a	For every additional Lead of 10 mts over and above initial lead of 10mt	Cum	20.00
	b	For every additional lift of 1.5mt over and above initial lift of 1.5mts	Cum	25.00
26		Labour charges for Spreading of silt unloaded by tractor in the field	Cum	29.71
27		Labour charges for breaking clods, trimming, sectioning and manual compaction using Dimmisa	Cum	46.28
	Pebble bunding			
28	a	Small stone (size more than 40mm) bunding- Labour charges for collecting and putting as bund only)	Cum	321.49

	Rough Stone Dry packing & Stone pitching (Unskilled)			
29	a	Rock Fill Dam, stone checks & Stone outlets- Labour charges for packing only)	Cum	306.18
	b	Stone terracing - Labour charges for packing only	Cum	306.18
	Plantation works			
		Category : I		
30		Survey and demarcation	100 Nos	39.74
31		Alignment and fixing of planting point with 0.45 meters length sticks	100 Nos	114.72
32		0.45 meter sticks preparation and transportation at site.	100 Nos	61.17
		i) Internal transportation of bag plants to planting points. (5"x9")	100 Nos	61.17
		ii) Internal transportation of Avenue Plantation. Tall plants	100 Nos	237.58
33		Refilling of Pits and planting (MxMxM), staking stick		
		i) 0.30 X 0.30 X 0.30 Size pit	each	1.42
		ii) 0.45 X 0.45 X 0.45 Size pit	each	4.47
		iii) 0.60 X 0.60 X 0.60 Size pit	each	9.12
		iv) 0.90 X 0.90 X 0.90 Size pit	each	13.67
		v) 1.00 X 1.00 X 1.00 Size pit	each	15.25
	Soil working and weeding			
34		**Category : I (1 M dia. and 0.1 m Depth)**		
	i	Avenue Plantation	each	15.25
	ii	Horticulture	each	15.25
35		**Category : II (0.5 M dia. and 0.1 m Depth)**		
	i	Fore shore plantation	each	4.50
	ii	B.H.Afforestation	each	4.50
	iii	Bio Diesel Plantation & Block plantation	each	4.50
36	**Causality Replacement for**			
	a	Reopening of Pits for avenue, Horticulture & Block Plantations.	each	15.51
	b	Fore share plantation, Barren Hill Afforestation, Bio-Diesel	each	7.54

37		Watch & Ward and repair to Fence and soil working of each plant including pruning of branches for plantations raised in common property resource lands and lands of SC/ST/assignees.	day	245.00
38	**Bio Fencing / Brush Wood Fencing for barren hill afforestation.**			
	a	Nurseries, block plantation and fore shore plantation including collection, transportation and fixing at site	Rmt	30.54
	b	Avenue Plantation including collection, transportation and fixing at site (Size of 1 m dia. and 1.5 m height)	each	115.83
	c	Horticulture, for lands of SC-ST & Assignee lands only	acre	3062.12
	d	Horticulture fencing 1st year & 2nd year maintenance SC-ST& Assignee lands only.	acre	765.50
39	**Deep Ploughing in**			
	a	Fallow Land and Hard Gravel soils (Depth not less than 0.3 meters) using ploughing tractors	acre	2023.81
	b	fallow land in ordinary soils using ploughing tractor depth not less than 0.3 m	acre	1619.58
	c	Cattle cultivator (Double ploughing) in ordinary soils.	acre	1216.18
40		Watering plants of block plantation from the sump constructed (where ever one sump is available per one acre)	plant	3.87
41		Watering plants from hand pump/bore well/open well up to distance of 30 mt	plant	5.45
42		Watering block plantation from the nearby sources i.e bore well open well or kunta beyond 30 mts distance.	plant	6.79
43		Hire charges of tractor mounted water tanker for filling sump- per one trip of 5000lit.	5000 lit	608.36
44		Sharpening of crowbar	day	15.00
45		Basket Replenishment charges	day	5.50

Note: Any rate not available in the above RSSR, the rates can be adopted from CSSR / FSR rate excluding contractor profit & overhead charges if any.

GOPAL KRISHNA DWIVEDI
PRINCIPAL SECRETARY TO GOVERNMENT